

level

Architectural Specifications for Level Window Films

PART 1: GENERAL

1.1 Summary:

Contractor shall furnish, install and finish Level Optically Clear Polyester Window Film and Perforated Window Film (hereafter Level Window Film) as specified in the contract documents.

1.2 Submittals:

For each type of Level Window Film material specified, the Contractor shall submit:

For Architect's approval, a sample, labeled with the appropriate material name and SKU information.

For Owner's approval, a copy of the maintenance instructions, as provided by Level.

1.3 Delivery and Storage:

All Level Window Films must be delivered to the job site in original packaging, properly identified and labeled.

Material must be stored in an undamaged condition in original packaging, maintained in a clean, dry, protected area where temperature and humidity remains stable and within the acceptable ranges for commercial window films.

All Level Window Films are to be inspected to verify that the delivered product is correct and that the color is accurate to what was ordered. Please see Section 3.2 for further details.

1.4 Project Conditions:

Environmental Conditions: Areas to receive Level Window Films should be environmentally controlled by the permanent HVAC system. Maintain a temperature range of 65 to 85 degrees Fahrenheit, with not more than 50% relative humidity and not less than what is specified for your area in the AWI Quality Standards Section 1700-T-19, for a period of not less than 4 days prior to installation and maintained thereafter.

Wall Conditions: Gypsum board finish shall be completed to comply with AWCI Specification, Level 4 or higher. Plaster walls shall be finished to the Architect's specification and be free of undulations and defects. See Manufacturer's Installation Instructions for additional details.

Lighting: The Contractor will provide sufficient lighting during the installation process. If required, temporary lighting will be provided to augment insufficient or low level permanent lighting.



Architectural Specifications for Level Window Films

PART 2: PRODUCT

2.1 Design Name: _____

2.2 Material Name: _____

2.3 Physical Properties:

Physical properties vary based on the selected material. Full specifications for all materials may be downloaded at www.findyourlevel.com.

2.4 Adhesive:

Level Window Films are self-adhesive products. Do not apply any additional adhesives to Window Films.

2.5 Warranty:

Level warrants its finished product to be free of manufacturing defects for a period of 90 days from the date that the finished product is received by the customer.

Please inspect all goods immediately upon receipt. Level is not responsible for labor charges, improper installation, installation of incorrect goods (those not approved or confirmed by the customer), removal of goods, or problems arising from defects in the construction, surface, or preparation of the wall.

Level retains all job files for one year. Printed goods (including strike-offs) older than one year will be discarded.

level

Architectural Specifications for Level Window Films

PART 3: EXECUTION

3.1 Level Window Films Shall be Applied by:

Window film installers having a minimum of three years experience, on projects of similar size and complexity to this project, installing commercial-grade self-adhesive window films and/or the following:

3.2 Inspection:

The Installer shall inspect all jobsite conditions and glass surface areas to receive Level Window Films. In the event that the Installer finds conditions detrimental to the installation process, the Installer will inform the Contractor and the Architect in writing. Work will not proceed until conditions have been corrected and accepted by the Installer, and at no additional cost to Owner.

Additionally, upon receipt Installer is to inspect all Level Window Films to verify:

- That the correct product was delivered
- That the color, scale, and design are accurate to what was ordered
- That the dimensions of the product correspond to those of the installation space
- That the product is free from defects
- That the alignment of the pattern across panels is correct

3.3 Surface Preparation:

Glass surfaces shall be clean, smooth and free from defects and imperfections as per Level's installation instructions.

3.4 Installation:

This is a custom made product and therefore its installation requires a higher attention to detail than installation of standard window film.

Window Film murals are shipped with unprinted selvage around all edges that requires trimming during installation.

Level will furnish detailed installation instructions and an installation diagram to the Installer. The installation instructions describe the process for applying the window film and the installation diagram illustrates the appropriate sequence of panel installation. Level is not responsible for improper installation or for installation that deviates from the recommendations provided in these installation documents.

Prior to installation, the installer shall lay out all of the panels in their correct sequence, using the included installation diagram as reference. This setup shall be used to determine the best starting point and help detect any problems that may arise during installation. The installer shall make sure that the window film will properly fit the installation area before beginning pasting.

© 4walls



Architectural Specifications for Level Window Films

3.4 Installation (continued):

Level Window Films shall be installed in strict accordance with the installation instructions and installation diagram included with the finished goods. Install each panel in sequential, numerical order as specified by Level in the installation diagram included with the finished goods.

If either the installation instructions or installation diagram are missing from the finished goods, stop and contact Level immediately to receive replacement documents.

Overage is added to each job to allow for double-cutting the seams between panels and to allow for trimming around the normal irregularities found at wall edges.

All Level Window Films murals will be produced accurately to the dimensions provided. Level will not be responsible for any variations between the dimensions provided and those of the actual installation site.

3.5 Clean Up and Protection:

Upon completion of installation, Installer will remove excess materials from the premises and leave the area in a clean and orderly condition.

Contractor will protect the finished window film from damage that may occur from other trades until project has been completed.

3.6 Maintenance:

Please see the installation instructions that are included with the finished goods.

Please contact your Level distributor for any assistance with this document.

Revised July 2025